



**NOTES:**

1. FOR SIDEWALK CONSTRUCTION DETAILS, SEE STANDARD 313
- △ 2. PROVIDE 1/2" PREFORMED BITUMINOUS EXPANSION JOINT MATERIAL AROUND ALL MAILBOXES, POWER POLES & FIRE HYDRANTS WITHIN THE SIDEWALK AREA.
- △ 3. PROVIDE 1/2" PREFORMED BITUMINOUS EXPANSION JOINT MATERIAL AT TRANSITION TO STANDARD WIDTH SIDEWALK.

REV.	DATE
△	1/20/16

<b>CONSTRUCTION STANDARDS</b>	<b>PAVING SIDEWALK OBSTRUCTIONS</b>	CITY OF FARMINGTON <hr/> PUBLIC WORKS DEPARTMENT
STANDARD No. D-318 SHEET 1 OF 1		

APPROVED *[Signature]* DATE 12/22/16